DETAILED ESTIMATE

BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:- Improvements to Roads and Drains at Gupta Layout and Surrounding Area Roads in Ward No 06 Thanisandra

								Estimation Cost.Rs	10000000
Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
1	**KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1) 5km lead= 57+2.0x1.28x5 =69.80**								
	New Drain								
	Gupta Layout								
	Main Road	Cum	1	221	1.2	1.05	278.46		
	Cross Road -1	Cum	1	107	1.05	1.05	117.9675		
	Cross Road	Cum	1	47.3	1.05	1.05	52.14825		
	Cross Road -4	Cum	1	126	1.05	1.05	138.915		
	New CC Culvert								
	Gupta Layout								
	Main Road	Cum	3	5	1.5	1.1	24.75		
	Cross Road -1	Cum	1	0	1.5	1.1	0		
	Cross Road -4	Cum	1	5.6	1.8	1.1	11.088		
	Cross Road	Cum	1	7.2	1.8	1.1	14.256		
	Basic rate	130							
	Area weightage 6%	7.8							
	5Km lead & Lift=57+(2*1.28*5	69.8							
	Sub Total	207.6							
	Total						637.58475	207.6	132362.5941
2	**KSRRB M2100 PCC 1 KSRRB M2100-10. Providing and laying Plain cement concrete of mix1:3:6 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days Including cost of materials,labour, HOM curing form work, Scaffolding and Centering complete as per specifications.MORTH Specification No. 2100 Pg no:222 Item no:27.18**								
	New Drain								
	Gupta Layout								
	Main Road	Cum	1	221	1.2	0.15	39.78		
	Cross Road -1	Cum	1	107	1.05	0.15	16.8525		
	Cross Road	Cum	1	47.3	1.05	0.15	7.44975		
	Cross Road -4	Cum	1	126	1.05	0.15	19.845		
	For New CC Culvert								
	Gupta Layout								
	Main Road	Cum	3	5	1.5	0.15	3.375		
	Cross Road -1	Cum	1	0	1.5	0.15	0		
	Cross Road -4	Cum	1	5.6	1.8	0.15	1.512		
	Cross Road	Cum	1	7.2	1.8	0.15	1.944		
	For CC Road								
	Gupta Layout								
	Main Road	Cum	1	221	4.7	0.15	155.805		
	Cross Road -1	Cum	1	107	6.3	0.15	101.115		
	Cross Road	Cum	1	47.3	4.6	0.15	32.637		
	Cross Road -4	Cum	1	126	4.3	0.15	81.27		
	Basic rate	5115							

No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
	Area weightage 6%	306.9							
	Sub Total	5421.9							
	Total						461.58525	5421.9	2502669.067
3	Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification No. 1500, 1700, 2200. Including Cost of material, Labour, HOM complete as per Specification-WALL & Bottom thickness 15Cm(Item No 37.59.2 page no 271)								
	New Drain								
	Bottom Raft								
	Gupta Layout								
	Main Road	Cum	1	221	1.2	0.15	39.78		
	Cross Road -1	Cum	1	107	1.05	0.15	16.8525		
	Cross Road	Cum	1	47.3	1.05	0.15	7.44975		
	Cross Road -4	Cum	1	126	1.05	0.15	19.845		
	Side Walls								
	Main Road	Cum	2	221	0.15	0.75	49.725		
	Cross Road -1	Cum	2	107	0.15	0.75	24.075		
	Cross Road	Cum	2	47.3	0.15	0.75	10.6425		
	Cross Road -4	Cum	2	126	0.15	0.75	28.35		
					Sub Total		196.71975		
	New Culvert								
	Bottom Raft								
	Gupta Layout								
	Main Road	Cum	3	5	1.5	0.2	4.5		
	Cross Road -1	Cum	1	0	1.5	0.2	0		
	Cross Road -4	Cum	1	5.6	1.8	0.2	2.016		
	Cross Road	Cum	1	7.2	1.8	0.2	2.592		
	Side Walls								
	Gupta Layout								
	Main Road	Cum	6	5	0.2	0.75	4.5		
	Cross Road -1	Cum	2	0	0.2	0.75	0		
	Cross Road -4	Cum	2	5.6	0.2	0.75	1.68		
	Cross Road	Cum	2	7.2	0.2	0.75	2.16		
					Sub Total		17.448		
	Basic rate	6670							
	Area weightage 6%	400.2							
	Sub Total	7070.2							
	Total						214.16775	7070.2	1514208.826
4	KSRB M2200-6 Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. MORTH Specification NO.1600&2200Specification No. Pg No.229 Item No.28.8.2								
	For Drain	Cum	From item no.3				196.71975		
		kg	Steel assumed 60Kg/Cum of Concrete				11803.185		
		tonne					11.803185		
	For Culvert	Cum	From item No 03				17.448		
		kg	Steel assumed 90Kg/Cum of Concrete				1570.32		
		tonne					1.57032		
	Basic rate	61365							

	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
	Area weightage 6%	3681.9							
	Sub Total	65046.9							
	Total						13.373505	65046.9	869905.0424
5	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)								
	Gupta Layout								
	Main Road	Cum	1	221	0.9		198.9		
	Cross Road -1	Cum	1	107	0.75		80.25		
	Cross Road	Cum	1	47.3	0.75		35.475		
	Cross Road -4	Cum	1	126	0.75		94.5		
	Data Rate	2337							
	Total						409.125	2337	956125.125
6	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incha								
	New Culvert								
	Gupta Layout								
	Main Road	Sqm	3	5	1.2		18		
	Cross Road -1	Sqm	1	0	1.2		0		
	Cross Road -4	Sqm	1	5.6	1.5		8.4		
	Cross Road	Sqm	1	7.2	1.5		10.8		
	Data rate	5418							
	Total						37.2	5418	201549.6
7	KSRRB M300-14. **Excavation for roadwork in all types of soil** by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specificatio MORTH Specification No.301Loading and unloading with 10km lead= (I No-19.14,P No-143)								
	For New CC Road								
	Gupta Layout								
	Main Road	Cum	1	221	4.7	0.45	467.415		
	Cross Road -1	Cum	1	107	6.3	0.45	303.345		
	Cross Road	Cum	1	47.3	4.6	0.45	97.911		
	Cross Road -4	Cum	1	126	4.3	0.45	243.81		
	Basic rate	41							
	Area weightage 6%	2.46							
	5Km lead=(2*1.28*5)	12.8							
	Sub Total	56.26							
	Total						1112.481	56.26	62588.18106
8	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications.(I No-19.64,P No-147)								
	Gupta Layout								
	Main Road	Sqm	1	221	4.7		1038.7		
	Cross Road -1	Sqm	1	107	6.3		674.1		
	Cross Road	Sqm	1	47.3	4.6		217.58		
	Cross Road -4	Sqm	1	126	4.3		541.8		
	Basic rate	6							
	Area weightage 6%	0.36							
	Sub Total	6.36							
	Total						2472.18	6.36	15723.0648

No	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
9	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications Clause 401 of MORTH V Revision.(I No-20.5,P No-153)								
	New Road								
	Gupta Layout								
	Main Road	Cum	1	221	4.7	0.15	155.805		
	Cross Road -1	Cum	1	107	6.3	0.15	101.115		
	Cross Road	Cum	1	47.3	4.6	0.15	32.637		
	Cross Road -4	Cum	1	126	4.3	0.15	81.27		
	Basic rate	1882							
	Area weightage 6%	112.92							
	Sub Total	1994.92							
	Total						370.827	1994.92	739770.1988
10	Cement concrete pavement.Construction of un-reinforced plain cement concrete for pavement, using a grade concrete M30 over a prepared base with OPC coarse aggregate @ 0.69cum fine aggregate @ 0.46cum,coarse and fine aggregate confirming to IS:383-2016,with superplastisiser @3lts confirming to IS9103-2008.mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine,and curing including cost of all materials,labour,hire charges of machineries,all lead and lift charges etc., complete as per specifications. - do with OPC at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.46cum Pg No.176Item No.22.6.1								
	Gupta Layout								
	Main Road	Cum	1	221	4.7	0.15	155.805		
	Cross Road -1	Cum	1	107	6.3	0.15	101.115		
	Cross Road	Cum	1	47.3	4.6	0.15	32.637		
	Cross Road -4	Cum	1	126	4.3	0.15	81.27		
	Basic rate	4916							
	Area weightage 6%	294.96							
	sub Total	5210.96							
	Total						370.827	5210.96	1932364.664
								Grand Total	8927266.363
								GST Charges (12% of estimated cost)	1071271.964
								Miscellenious and rounding	1461.673295
								Total Amount	10000000
								RUPEES ONE CRORE ONLY	

ADMINISTRATIVE APPROVAL
Accorded For Rs. 100 lakhs only
Head of A/c P3075
Adv. Ref. No. 23/2024 Date 25/8/2020
AE 24/01 EE(BTP)

for Rs. 100.00 LAKH
HUNDRED LAKH ONLY
Registered under Sec.(Y)/TS/ 12 /2024-25 subject to conditions contained in enclosed memo No 12 /2024 Dated. 26/8/2020
SE(Yelahanka)
AE/JE TA

CERTIFICATE:
1) The work spot has been inspected and found to be necessary
2) The work spot comes under B.B.M.P
3) The provisions made in the estimate are necessary and minimum
4) The estimate is based on C.S.R of 2018-2019,Issue rates and Data Rates

Assistant Engineer
BBMP

Assistant Executive Engineer
BBMP

Executive Engineer
BBMP